



**Vicinity Map**  
Scale: 1" = 2000'

**Erosion and Sediment Control Notes**

1. Unless otherwise indicated, all vegetative and structural erosion and sediment control practices will be constructed and maintained according to the minimum standards and specifications of the "Virginia Erosion and Sediment Control Handbook" and Virginia Regulations 4VAC50-30: Erosion and Sediment Control Regulations, and Chapter 8 of the Code of James City County.
2. The Resource Protection Division of James City County must be notified one week prior to the pre-construction conference, one week prior to the commencement of land disturbing activity, and one week prior to the final inspection.
3. All erosion and sediment control measures are to be placed prior to or as the first step in clearing.
4. Land disturbing activities in other areas of the subdivision (Lots 1-5) will be controlled by erosion and sediment control measures indicated on the individual site plans for each lot. The individual Site Plans for Lots 1 through 5 will be submitted to the James City County Engineering and Resource Protection Division prior to construction. This plan only pertains to erosion and sediment control measures associated with the use-in-common driveway crossing Lots 4 and 2, and the entrance to the site from Jolly Pond Road.
5. The contractor is responsible for installation of any additional erosion control measures necessary to prevent erosion and sedimentation as determined by inspection by James City County.
6. All disturbed areas are to drain to approved sediment control measures at all times during land disturbing activities, and during site development until final stabilization is achieved.
7. The contractor shall inspect all erosion control measures periodically and after each runoff-producing rainfall event. Any necessary repairs or cleanup to maintain the effectiveness of the erosion control devices shall be made immediately.

**General Notes:**

- 1) This site plan was produced without the benefit of a title report. All easements may not be shown.
- 2) The subject property is Outside the JCC Primary Service Area. The subject property shall be served by private water and sewer.
- 3) All new utilities are to be placed underground.
- 4) The shared private entrance to lots 1, 2, 3, 4, and 5 will follow the private and low volume commercial entrance standard in the VDOT Road Design Manual, Appendix F, p. F-104 to p. F-107.
- 5) Existing site topography based on James City County GIS and additional field run surveys
- 6) Property is zoned A1.
- 7) Owner/Developer: Thomas B. Wallace (d) and Evangeline Wallace (Trustee)  
Inst. 090009180



**Additional Notes:**

1. All erosion and sediment control measures must be in place and approved by James City County prior to beginning any land disturbance activities.
2. A Stabilized Construction Entrance will be constructed and maintained throughout the period of construction. At substantial completion, the Stabilized Construction Entrance will be replaced by an Asphalt Driveway Apron, as indicated hereon.
3. The shared driveway will have a paved surface at least 15 feet wide consisting of two inches of pavement over four to six inches of stone aggregate, in accordance with Section 19-73(b) of the Subdivision Ordinance.
4. The Asphalt Driveway Apron will be constructed in conformance with the Virginia Dept. of Transportation - Road Design Manual, Subdivision Street Design Guide.
5. Soils inspections for this site were provided by Gregory T. Monnett, Ph.D., LPSS. Details of the soils analysis are provided in the soils report provided to James City County, under separate cover.

Legend	
●	Rod Found
○	Rod Set
•	Record Data
LOD	Limits of Disturbance
SF	Silt Fence
SCE	Construction Entrance
→	Drainage Flow Direction
XXX.X	Ex. Spot Elevation
XXX.X	Proposed Spot Elevation

2 Large/Small Plat(s) Recorded  
herewith as # 190000629

City of Williamsburg & County of James City  
Circuit Court; This PLAT was recorded on  
1-5-2019  
at 11:30 AM PM, PG. PG.  
Document # 190000629  
MONA A. FOLEY, CLERK  
Mona Foley, Clerk

**Erosion and Sediment Control Plan For Shared Driveway**




(804) 370-2551 ■ FAX (804) 966-2820  
www.gardysurveying.com  
P.O. Box 15 ■ New Kent, VA 23124



**Minor Subdivision: #3150 Jolly Pond Road**

Property of: Thomas B. Wallace(d) and Evangeline Wallace (Trustees)  
Parcel I.D.: 3030100021; LRSN: 1116  
Inst. 090009180  
Powhatan District, James City County, Virginia



MAG. DISTRICT: Powhatan	COUNTY: James City
DATE: August 10, 2018	SCALE: 1"=100'
SHEET: 2 OF 2	J.N.: 18-0010
DRAWN BY: RJL	CHECKED BY: DRG
ESC Case # 5-18-0028	JCC Case # 5-18-0036
REV.	DATE
Per County Comments	September 11, 2018
Per County Comments	October 4, 2018
Per County Comments	November 21, 2018