Williamsburg/James City County
Recorded 16th day of January 2001
in Deed Book 84 page 602
Teste: Beth W. Polkinghorn Clerk

#02000 84 PAGE 602

FINISH SCHEDULE

ROOM NAME	FLOORS	BASE	WALLS	C.G MAT.	C.G HT
RECEPTION	CARPET	PAINT	PAINT	PAINT	9'-0"
CONFERENCE ROOM	CARPET	PAINT	PAINT	PAINT	9'-0"
HCP TOILETS	CER. TILE	PAINT	PAINT	PAINT	9'-0"
HALLS	CARPET	PAINT	PAINT	PAINT	9'-0"
OFFICE #1	CARPET	PAINT	PAINT	PAINT	9'-0"
OFFICE #2	CARPET	PAINT	PAINT	PAINT	9'-0"
OFFICE #3	CARPET	PAINT	PAINT	PAINT	9'-0"
OFFICE #4	CARPET	PAINT	PAINT	PAINT	9'-0"
OFFICE #5	CARPET	PAINT	PAINT	PAINT	9'-0"
OFFICE #6	CARPET	PAINT	PAINT	PAINT	9'-0"
LOUNGE	CARPET	PAINT	PAINT	PAINT	9'-0"
COPY ROOM	CARPET	PAINT	PAINT	PAINT	9'-0"
SUITE 1-a	CARPET	PAINT	PAINT	PAINT	9'-0"
SUITE 1-b	CARPET	PAINT	PAINT	PAINT	9'-0"
JANITOR	VINYL	PAINT	PAINT	PAINT	9'-0"

DOOR SCHEDULE

SYM	SIZE	THK	DOOR MTL	FRAME MTL	NOTES	HDW SET
1	3'-0"x7'-0"	1 3/4"	CLAD WD	PAINT	1	A
2	(2) 3'-0"x7'-0"	1 3/4"	PAINT WD	PAINT	2	B
3	3'-0"x7'-0"	1 3/4"	PAINT WD	PAINT	3	C
4	3'-0"x7'-0"	1 3/4"	PAINT WD	PAINT	2	B
5	3'-0"x7'-0"	1 3/4"	PAINT WD	PAINT	3	C
6	3'-0"x7'-0"	1 3/4"	PAINT WD	PAINT	3	C
7	3'-0"x7'-0"	1 3/4"	PAINT WD	PAINT	3	C
8	3'-0"x7'-0"	1 3/4"	PAINT WD	PAINT	4	D
9	3'-0"x7'-0"	1 3/4"	PAINT WD	PAINT	4	D

DOOR SCHEDULE NOTES

1. DOOR SET C IS FOR USE IN HCP TOILET ROOMS ONLY.
2. FRAMES IN HCP TOILET ROOMS TO BE PAINTED WOOD.
3. FRAMES IN OFFICE AREAS TO BE PAINTED WOOD.
4. FRAMES IN JANITOR CLOSET TO BE PAINTED WOOD.

DOOR HARDWARE SETS

HARDWARE SET 'A' - 3 PAIR HINGES, 1 MAN/PASS PASSAGE LOCKSET, 1 CLOSER, 1 KICK PLATE, 1 WALL STOP, 1 SET OF SILENCERS.

HARDWARE SET 'B' - 6 PAIR HINGES, 1 MAN/PASS PASSAGE LOCKSET, 2 CLOSERS, 2 KICK PLATES, 2 WALL STOPS, 1 SET OF SILENCERS.

HARDWARE SET 'C' - 1.5 PAIR HINGES, 1 PRIVACY LOCKSET.

HARDWARE SET 'D' - 1.5 PAIR HINGES, 1 PASSAGE LOCKSET.

HARDWARE SET 'E' - 1.5 PAIR HINGES, 1 PASSAGE LOCKSET, 1 CLOSER.

HARDWARE SET 'F' - 1.5 PAIR HINGES, 1 MAN/PASS PASSAGE LOCKSET, 1 CLOSER, 1 KICK PLATE, 1 WALL STOP, 1 SET OF SILENCERS.

WINDOW SCHEDULE

SYM	SIZE	TYPE	GLASS	FRAME MTL	HD HT AFF	NOTES
A	3'-0"x5'-0"	CASEMENT	INSUL	CLAD WD	6'-0"	
B	(2) 3'-0"x5'-0"	CASEMENT	INSUL	CLAD WD	6'-0"	1

WINDOW SCHEDULE NOTES

1. PROVIDE CLAD WOOD CASEMENT WINDOWS WITH INSULATED GLASS.
2. PROVIDE OPERABLE CLAD WOOD CASEMENT WINDOWS WITH INSULATED GLASS.

INTERIOR ELEVATIONS

SUITES 1-a & 1-b

JIM GRIFFITH BUILDER INC.
PHASE 10 - VILLAGE AT CHERRY AND CONWAY
WILLIAMSBURG, VIRGINIA

DAVID R. DRE ARCHITECT, P.C.